

# **KENTWOOD NORTHEAST**

**(KINGSGATE)**

## **NEIGHBOURHOOD AREA STRUCTURE PLAN**

**Prepared for**

**Laebon Developments Ltd.  
and  
Quantum IV Developments Inc.**

**Adopted as a bylaw September 1998  
Amended August 2003  
Amended August 2004  
Amended July 2005  
Amended September 2005  
Amended March 2021  
Amended June 2023 (Bylaw 3217/A-2023)**

## Table of Contents

1.0	Introduction	
1.1	Location and Ownership	1
1.2	Ownership - 2022	1
2.0	Site Characteristics	
2.1	Existing Land Use	5
2.2	Natural Features	5
2.3	Servicing	8
2.4	Access	8
2.5	Emergency Services	9
2.6	Environmental Assessment	9
2.7	Noise Recommendations	9
3.0	Development Concept	
3.1	Land Use Distribution	12
3.2	Residential	12
3.3	Commercial	12
3.4	Density	12
3.5	Open Space	13
3.6	Social Facilities	15
3.7	Transportation	15
4.0	Municipal Servicing	
4.1	Water Mains	18
4.2	Sanitary Sewer	18
4.3	Storm Sewer	18
4.4	Power, Telephone and Cable Vision	19
4.5	Natural Gas	20
5.0	Staging of Development	25

## **LIST OF FIGURES**

Figure 1	Location Plan
Figure 2	Ownership (2022)
Figure 3	Natural Features
Figure 4	Land Use Distribution
Figure 5	Water Distribution
Figure 6	Sanitary Sewers
Figure 7	Storm Sewers
Figure 8	Overland Drainage
Figure 9	Phasing
Figure 10	Pedestrian Circulation

## **LIST OF TABLES**

Table 1	Neighbourhood Area Structure Plan Statistics
Table 2	Dwelling Units and Density

## **LIST OF APPENDICES**

Appendix A	North Kentwood Natural (Ecospace) Area
Appendix B	Park/School Site Development Concept

## **1. INTRODUCTION**

This Neighbourhood Area Structure Plan was originally prepared in September of 1998 on behalf of Laebon Developments Ltd. and Quantum IV Developments Inc. in accordance with the City of Red Deer's 1996 Planning and Subdivision guidelines and as a precondition for redesignation and subdivision.

In June 2003 it was revised to change road patterns on the lands owned by 957292 Alberta Ltd. (Laebon), to add a small piece of land to the west of the subject site and to indicate utilities installed up to that date. The January 2002 version of the City of Red Deer Planning and Subdivision guidelines was applied to the update.

In 2023, an amendment was completed to introduce a multi-family site and update the status of a wetland, both shown in the northeast corner of the Plan area. The multi-family site is in a portion of undeveloped land that was previously identified as commercial. The entirety of the wetland has had compensation paid for it by the City to the Province to accommodate the Highway 11A road widening.

### **1.1 Location**

The land is generally located west of Gaetz Avenue, south of Highway 11A, southeast of the Canadian Pacific Railway and north of the existing Kentwood subdivision (as shown on Figure 1).

### **1.2 Ownership - 2022**


The majority of the Plan area has been developed as of 2022. As shown on Figure 2, one parcel in the northeast is currently undeveloped and owned by Kingswood Crossing (Alberta) Inc.

The plan area is 47.35 ha (117.0 ac) .

- Developed Area: 40.96 ha (101.2 ac), owned by various private entities
- Undeveloped Area: 6.39 ha (15.8 ac), owned by Kingswood Crossing (Alberta) Inc.

**Table 1: Plan Statistics**


	<b>Ha</b>	<b>% NDA</b>
<b>Gross Plan Area</b>	<b>47.35</b>	<b>100.0%</b>
Residential	23.03	48.6%
R1	10.20	21.5%
R1N	7.70	16.2%
R1A	3.35	7.1%
R2	0.08	0.2%
R3	1.70	3.6%
Commercial	4.68	9.9%
Church	0.41	0.9%
Social Care	0.12	0.2%
Open Space	7.45	15.7%
Transportation	11.66	24.7%
<b>Total</b>	<b>47.35</b>	<b>100.0%</b>



KENTWOOD NORTHEAST (KINGSGATE)

FIGURE 1: LOCATION

SCALE = 1:10000



# KENTWOOD NORTHEAST (KINGSGATE)


## FIGURE 2: OWNERSHIP (2022)

SCALE = 1:5000



	FUTURE DEVELOPMENT
	DEVELOPED
	NASP BOUNDARY

KINGSWOOD  
CROSSING  
(ALBERTA) INC.



July, 2022

## 2.0 SITE CHARACTERISTICS

### 2.1 Existing Land Use

At the time of plan adoption, the Plan area was designated A-1, Future Urban Development District under the City of Red Deer Land Use Bylaw 3156/96. The general purpose of this district was to ensure that development on lands required for future urban development is restricted to ensure that future development may proceed in an orderly and well-planned fashion, in keeping with the intent of the Municipal Development Plan”.

The Plan area is situated within the boundary of, and is consistent with the objectives of the Northwest Area Structure Plan.

Redesignation to appropriate residential and commercial land use districts will be required before development can occur.

### 2.2 Natural Features

This Neighbourhood Area Structure Plan encompasses lands which are generally flat with elevations ranging from a high point of 881 meters on the west portion to a low point of 874 meters on the east portion (see Figure 3). The Plan area is presently a mixture of cultivated land, tree covered areas and wetlands.

The City of Red Deer’s Ecological Profile of the North Kentwood Natural Area identified five zones within the Neighbourhood Area Structure Plan area (Appendix A), and provided priority rankings for each zone, for the preservation of natural areas (A is top priority, C is low priority).

**Zone 6 (old drive-in site) – Priority A – Recommendation R1.** The area is covered by a sporadic growth of poplars intermixed with willows which also line the eastern part of the section. The area is characterized by diverse vegetative growth and is populated by a wide variety of birds. The profile encourages the preservation of as much of the natural habitat as possible.

Wetland areas may be removed or modified for stormwater for this area. The City paid compensation for this wetland during the road widening of Highway 11A.

City Parks department staff would like an opportunity to remove orchids from the site prior to development if the Owner has no plans to preserve them or relocate or use these plants.



# KENTWOOD NORTHEAST (KINGSGATE)


## FIGURE 3: NATURAL FEATURES

SCALE = 1:5000



ROAD ALLOWANCE

- CONTOUR LINE
- 877 CONTOUR ELEVATION
- NASP BOUNDARY



July, 2022

**Zone 7 – Priority A – Recommendation R2.** A large mature northwest poplar wind break lines the north boundary of a commercial sales lot at the north end of Zone 7. The western edge of the commercial lot is lined with Manitoba maple, aspen, balsam and willow. A stand of mixed poplar trees runs north and south connecting Zones 6 and 7 along the boundary between the commercial lots on the west side of Gaetz Avenue and the Neighbourhood Area Structure Plan area. The profile encourages preservation of mature poplar tree stands running east and west located at the north and south ends of Zone 7. The ecological profile recommends retaining the tree stands in their entirety for use as entrance features at the collector road accesses into the neighbourhood.

The Kingston Drive/Gaetz Avenue intersection requires that additional lands be obtained from third party landowners. The City of Red Deer has developed a roadway concept for this intersection. Only those trees which need to be removed to accommodate construction of the roadway will be cleared.

Much of the poplar wind break identified along the west edge of the existing commercial area lies in a buffer area identified in the Neighbourhood Area Structure Plan. Only the portion of that site at the south end of the buffer (east of the proposed worship space site and within the worship space site) has been deemed possible to preserve of.

**Zone 8 – Priority B – Recommendation R3.** This area is primarily made up of a large tree stand surrounded by a cultivated field. The north and west sides of the zone contain many aspen, poplar and various willow species, while the east side consists of mixed poplars and a few spruce trees. The profile recommends that the southeast portion of the poplar trees be incorporated into residential housing where possible. The north side of the zone extends into properties outside of the boundaries of the Neighbourhood Area Structure Plan area. As of January 2003, these tree stands had been eliminated by site grading of the plan area.

**Zone 12 – Priority A – Recommendation R4.** A small band of poplar trees on the south portion of the area should be dedicated as a walkway lot and municipal reserve.

This zone lies on the south edge of the proposed park/school site and it is feasible to retain a portion of the stand during development of the park/school site. Where the zone extends eastward from the school site along the rear of proposed residential lots, a four (4) metre wide municipal reserve is provided for. It is understood the services for the proposed

residential lots will be extended from the south side to the north side of the four metre treed municipal reserve. The services will be extended through the four metre strip by clearing only those trees which must be cleared to facilitate the lot servicing.

**Southeast Wetland – Priority B – Recommendation R5.** The area contains a dugout and drainage channel surrounded by semi aquatic grasses and a number of good quality willows and is part of a habitat area that was removed in 1997. The profile encourages preservation of this area and incorporation into future development as a linear drainage channel and passive walking area or incorporation into a future buffer.

Preliminary site grading in 2001 eliminated much of the wetland.

### **2.3 Servicing**

Existing municipal water, sewer and storm sewer facilities are in place on three sides of the Neighbourhood Area Structure plan area. Water mains, sanitary sewer trunks and mains and storm sewer trunks and mains will be extended through the Neighbourhood Area Structure plan area to enable servicing of properties to the north which are not part of this Neighbourhood Area Structure Plan. The municipal services will be constructed of such size and capacity to ensure that existing facilities which are located at the boundaries of the Neighbourhood Area Structure Plan are fully utilized.

It is the intent of the Owners of the Neighbourhood Area Structure Plan properties to maximize the potential for future development of properties outside the plan area by constructing water, sanitary sewer and storm sewer trunks and mains which can provide service to properties beyond their own.

The site can be serviced with municipal water, sanitary sewer and storm water utilities. An engineering study, required to establish the details of servicing, has been completed and supplied to the City of Red Deer, Engineering Department under separate cover.

### **2.4 Access**

The plan area can be accessed via Kingston Drive in the west and Kentwood Drive in the southeast.

## **2.5 Emergency Services**

The Neighbourhood Area Structure Plan area currently has an estimated Emergency Services response time of greater than six and one half (6.5) minutes.

## **2.6 Environmental Assessment**

A level 1 Environmental Assessment has been completed by UMA Engineering and submitted to the City of Red Deer under separate cover. The environment site assessment revealed no significant sources of contamination of the subject property.

Based on the proximity to the industrial/commercial uses to the east, the report encourages further investigation to monitor the impact of nearby commercial land uses and to study the migration of potential contaminants from nearby quarter sections. Monitoring of the areas adjacent to commercial subdivisions where contaminants could originate will continue as development proceeds and encroaches on those areas.

## **2.7 Noise Recommendations**

In 1999, the City of Red Deer undertook a study of noise levels in the Kentwood area. The study concluded that lands adjacent to the rail track and adjacent to the Edgar Industrial Area exceeded 60 dBa, which is the level deemed by the City of Red Deer to be the maximum acceptable. As a result of the report, the City and Neighbourhood Area Structure Plan landowners agreed to the following strategies to mitigate the effect of the noise on homeowners.

### **2.7.1 Barrier Height**

The berm adjacent to the rail line is required to be a minimum of four metres high. Further, there is to be two metre high noise attenuation fence constructed on top of the berm. The berm will be landscaped to standards set by the City of Red Deer.

### **2.7.2 Barrier Block Construction Techniques**

All homes adjacent to the rail are to incorporate barrier block construction techniques to mitigate against noise effects.

#### **2.7.2.1 Construction Details**

All homes adjacent to the rail line are to incorporate the following construction aspects:

- 2 x 6 walls
- R24 insulation
- Double glazed windows

### **2.7.2.2 Home Design Considerations**

The report suggests that in the first row of homes adjacent to the rail line, that noise sensitive rooms such as bedrooms could be located on the side of the home furthest from the rail line/industrial areas. This is not a requirement; it is only a suggestion.

### **2.7.2.3 Construction Initiatives**

The reports author offers a number of other ideas that might be incorporated into home construction. He suggests central air conditioning might eliminate the need to open windows. Another is reducing the height of buildings, as bungalows will be better sheltered behind the berm.

# KENTWOOD NORTHEAST (KINGSGATE)

## FIGURE 4: LAND USE


SCALE = 1:5000



Note: Any reference to a specific school authority in this plan is only an indication of a school authority's site preference. The allocation of identified school sites will be determined by the Joint Use Committee. (Bylaw 3217/B-2021)

### LAND USE LEGEND

R1		PLACE OF WORSHIP	
R1A		COMMERCIAL	
R1N		MUNICIPAL RESERVE	
R2		SOCIAL CARE	
R3		NASP BOUNDARY	



## **3.0 Development Concept**

The proposed Neighbourhood Area Structure Plan incorporates policies contained in the Northwest Area Structure Plan and other City of Red Deer guidelines and policy documents.

### **3.1 Land Distribution**

The land use and development concept proposed for the Neighbourhood Area Structure Plan area is shown on Figure 4. The majority of the plan area is proposed for single family residential with some semi-detached development. The northeast portion of the plan area proposes commercial and multi-family uses. The proposed land use distribution is shown in Table 1.

### **3.2 Residential**

The residential areas will consist mainly of R1 and R1N single detached dwellings with some areas zoned R1A which will accommodate semi-detached dwellings. There is a small area in the southeast corner which abuts an existing R2 townhouse community that will accommodate a few townhouse units. A R3 site will also be included in the northeast, adjacent to the commercial site.

### **3.3 Commercial**

A 4.68 ha (11.6 ac) area in the northeast portion of the plan area is proposed for C2A - Commercial (Regional Shopping Centre) District zoning. Development of the commercial property shall be complimentary to the residential development to the west. Uses such as nightclubs and licensed lounges, other than those ancillary to restaurants, which may have a detrimental noise impact, will not be allowed.

Landscaping and/or screening shall be used to enhance the visual appearance of the commercial development, as viewed from other areas. Landscaping and/or screening will also be used to control the noise impact of commercial development on the residential development.

### **3.4 Density**

Including all the lots developed since this plan was adopted in September 1998, and assuming the undeveloped areas are developed as per this plan, it is estimated that this Neighbourhood Area Structure Plan area will accommodate 155 single family R1 lots, 220 single family R1N lots, 140 semi-detached and 150 multi-family dwellings.

If the areas slated for use as day care, social care or retirement home site and place of worship are eventually used for development of housing (R1N or R1A), the population density in the area will increase. The commercial areas and lands

dedicated to the City of Red Deer as municipal reserve from neighboring developments have not been included in the density calculations. Density for the Kentwood Northeast will be 14.04 dwelling units per hectare.

**Table 2: Dwelling Units and Density**

Land Use	Units	Pop/Unit	Population
R1	155	3.5	543
R1N	220	3.5	770
R1A/R2	140	2.5	350
R3	150	1.5	225
<b>Total</b>	<b>665</b>		<b>1888</b>
<b>Persons/ha</b>			<b>39.86</b>
<b>Units/ha</b>			<b>14.04</b>

### 3.5 Open Space

The proposed park and open space system includes a neighbourhood park/school site, walkway, a separate municipal reserve parcel and a buffer area. A total of 15.7% of the plan area will be dedicated to municipal reserve.

#### 3.5.1 Neighbourhood Park/School Site

A neighbourhood park/school site is proposed in the central area of the Neighbourhood Area Structure Plan area to accommodate a school and related playground facilities as identified in the Northwest Area Structure plan. The overall site is proposed to be 5.42 ha (13.4 ac).

A development concept of the park/school site has been prepared by the City of Red Deer and has been provided as Appendix B. An integral part of the development concept is the storm water detention pond which will encompass the sports fields planned for the park (in particular the ball diamond and soccer pitch).

The school site will be zoned PS (public service). While the maps indicate that it will be a public K-8 (kindergarten to grade 8) school, it may be any combination of grades between kindergarten and grade 8.

Any reference to a specific school authority in this plan is only an indication of a school authority's site preference. The allocation of identified school sites will be determined by the Joint Use Committee. (Bylaw 3217/B-2021)



### **3.5.2 Municipal Reserve Parcels**

There are a number of municipal reserve parcels throughout the Neighbourhood Area Structure Plan area.

#### **3.5.2.1 Link from neighbourhood park/school site to the east**

A ten metre wide walkway 0.04 ha (0.1 ac) extending easterly from the school site to the residential area is proposed to connect the school site to the residential development. It will include a 1.5 metre walking trail.

#### **3.5.2.2 Link from Kerr Close to the West**

There is a six metre wide link between the west side of Kerr Close and the neighbourhood park/school site to the west. The area of this link is 0.02 ha (0.05 ac). The M-R strip will be landscaped to ensure access from the residential areas to the park.

#### **3.5.2.3 Railway Area**

A total of 0.41 ha (1.0 ac) of municipal reserve will be incorporated into the berm separating residential development from the Canadian Pacific Railway.

#### **3.5.2.4 East Boundary of Residential Area**

The total area of this reserve parcel will be 0.75 hectares (1.9 ac). The residential areas on the east edge of the property abut commercial lots fronting Gaetz Avenue. They will be separated by a ten metre wide municipal reserve. A treed berm will be constructed on the reserve. The berm will extend south from the south side of the future location of Kingston Drive to the north end of the proposed place of worship site. There are some trees on the place of worship site, and they will be left by the developer. This reserve will include a segment which will extend from 52 Street to the Gaetz Avenue Service Road which will be left in its present state.

#### **3.5.2.5 South Boundary of Residential Area**

An MR parcel of 0.05 ha (0.1 ac) will be created to link the neighbourhood park/school site to Kentwood Drive. This parcel will be four metres wide, and will be left as natural as possible. Utilities will have to be constructed through the area.

### **3.5.3 Wetlands**

The wetland area in the northwest corner of the Kingswood Crossing (Alberta) Inc. parcel will be impacted or removed by the Highway 11A road widening. Compensation has been paid by the City of Red Deer for this wetland.

## **3.6 Social Facilities**

In accordance with the City of Red Deer's planning and subdivision guidelines, a site has been provided which is suitable for either a day care, social care residence or a retirement home, as well as a site for a place of worship.

### **3.6.1 Day Care/Social Care or Retirement Home Facility**

The 0.12 ha (0.3 ac) site provided in the plan area is adjacent to an intersection of two collector roadways and is approximately 400 metres from the designated school site. Should a day care, social care facility or retirement home not be constructed, the site will be suitable for R1N zoning (single family dwellings).

### **3.6.2 Place of Worship Site**

The 0.41 hectare (1.0 acre) designated place of worship site is at the south east corner of the site, between 52 Avenue and Kentwood Drive. If the site is not required for a place of worship it is suitable for R1A (duplex) zoning.

## **3.7 Transportation**

### **3.7.1 Collector Roadways**

The Neighbourhood Area Structure Plan contains collector roadways aligned in accordance with the Northwest Area Structure Plan.

The plan continues the collector roadway concept contained in the Kentwood West Neighbourhood Area Structure Plan and existing subdivisions to the south. There are three collector roads in the plan area.

#### **3.7.1.1 Kingston Drive**

The main collector roadway is a continuation of the existing Kingston Drive and is proposed to circle through the area from Kelly Street to a proposed intersection at Gaetz Avenue at the northeast corner of the plan area.

To complete the connection of the Neighbourhood Area Structure Plan to Gaetz Avenue in the north east corner of the proposed development, Kingston Drive will be constructed on lands which are not presently owned or controlled by either of the owners of the lands which are the subject of this plan. In order for this plan to be effectively implemented, land required to complete the connection of Kingston Drive to Gaetz Avenue must be obtained by the Owners of the plan lands. The City of Red Deer will assist Laebon Developments Ltd. and Quantum IV Developments Inc to obtain the lands owned by others under terms that are timely, fair and equitable.

Access type, number of accesses and access spacing will be determined in consultation with Engineering Services during the update of the Servicing Study.

#### **3.7.1.2 Kentwood Drive**

Kentwood Drive presently terminates at the south side of the Plan area. It will be extended north through the plan area to connect with the future extension of Kingston Drive.

#### **3.7.1.3 Kendrew Drive**

Kendrew Drive extends west from Kingston Drive to residential development to the west.

### **3.7.2 Transit Stopping Zones**

Where transit stopping zones are required along collector roads, efforts will be made by the developers to orient corner lots so that stopping zones will be provided at the side of the lots rather than at the front.

### **3.7.3 Local roadways**

The system of local roadways provides access to individual lots throughout the plan area. Detailed drawings indicating road widths will be prepared and submitted to the City of Red Deer Engineering Services, prior to development.

### **3.7.4 Laneways**

The majority of lots within the plan area back onto lanes. A few lots with rear yards adjoining the boundary of the neighbourhood park/school site will not have lane access. Also, some lots which back onto the 4.0 metre treed walkway between the proposed residential development and the laneway in the existing Kentwood subdivision will have restricted lane access.

### **3.7.5 Pedestrian and Bicycle Circulation**

The sidewalks proposed to be developed within the road right of ways combined with the proposed reserve dedication will link the residential areas to the major park features proposed for the plan area and adjacent lands. There is potential for bicycle-pedestrian pathways through the park/school site.

The proposed location for the bicycle-pedestrian pathway is shown on the development concept drawing for the park/school site, prepared by the City of Red Deer, and included as Appendix A.

An additional Municipal Reserve parcel will ensure access from Kerr Close to the park area/school site to the west.

Within the right-of-way of Kingston Drive, adjacent to the west boundary of the park/school site a 1.5 metre wide bicycle path/walkway will provide pedestrian access to lands north of the plan area.

## **4.0 Municipal Servicing**

The Kentwood Northeast Neighbourhood Area Structure Plan area is serviced from existing sanitary sewer and water mains located at the southern boundaries of the Kentwood East properties.

### **4.1 Water Mains**

The Kentwood Northeast Neighbourhood Area Structure Plan will be serviced by water from four locations. The existing 300 mm westerly main, located within the Kennedy Drive right-of-way has been extended along the west side of the site to service early phases of area. The existing 150 mm main located on the east side of Kentwood phase 5E will be extended to complete looping.

The existing 200 mm main located along the eastern boundary of the proposed storm dry pond will be extended. The existing 200 mm easterly service located on Kentwood Drive will be extended north.

The water distribution network will be designed to accommodate all future development areas in the Neighbourhood Area Structure Plan area and those areas which have not been included as part of this plan lying between Kentwood Northeast and Highway 11A which may be developed in the future. Looping of mains and cross connections to existing development areas will be completed as necessary to provide an efficient system with adequate fire flows. Figure 5 schematically shows the network of proposed water mains.

### **4.2 Sanitary Sewers**

The Kentwood Northeast Area Structure plan area will be serviced by sanitary sewer from three main locations. The westerly connection will be made to a 450 mm main in the Kennedy Drive right-of-way. Another connection to a 200 mm main located on the east side of Kentwood phase 5E will be completed to service phase one and two. The easterly connection will be to a 300 mm main located on Kentwood Drive. The sewer has the capacity to serve the entire catchment area. Figure 6 schematically shows the proposed routing of the sanitary sewer system.

All sanitary sewers will be seated and installed in a suitable bedding material in order to provide long terms stability to the pipe. Pipe type will be specified to prevent the ingress of ground water to the system.

### **4.3 Storm Sewer System**

#### **4.3.1 Minor System**

Run-off storms up to the one in five year event will be conveyed by gravity via a piped system to two connections to the existing system. The westerly

connection is a 1500 mm storm main located in the Kennedy Drive right-of-way and the easterly connection is a 1200 mm main in Kentwood Drive.

The commercial and multi-family site may require onsite stormwater storage. Additional consideration and details will be determined as part of the servicing study.

Figure 7 schematically shows the routing of the storm sewer system. Pipe sizes and materials will be designed in accordance with the City of Red Deer Design guidelines.

#### **4.3.2 Major System**

For storm events in excess of a one in five year event, roads and laneways will be designed to convey overland flows to storm water ponds located in the northwest and the south central part of the plan area.

Ponding of within roadways or lanes will be permitted in strict accordance with the City of Red Deer design guidelines. Area drainage and overland flow routes are indicated schematically on Figure 8.

#### **4.4 Power, Telephone and Cable Vision**

Red Deer Electric Light and Power, Telus and Shaw Cable advise that their networks have sufficient capacity, with some qualification regarding the sequencing of phasing, to fully develop the proposed Kentwood Northeast Neighbourhood Area Structure Plan development.

The City of Red Deer Electric Light and Power department has advised that two main utility lines will require underground alignments on the west side of Gaetz Avenue between 80<sup>th</sup> Street and Highway 11A. The utility lines will also require an alignment westward from Gaetz Avenue along a portion of Highway 11A. The underground alignments are required prior to the development of the commercial areas indicated as phase 5 of the plan.

A third main line will be required to service phases 4,5 and 6. This third main line will follow an alignment from 80<sup>th</sup> Avenue (at Gaetz Avenue) and along Kingston Drive. Expansion of the existing system will be required to complete the phase 1,2 and 3 development. This expansion will include switchgear alignments currently presumed to be required in the northwest and southwest corners of the park/school site and at Kingston Drive, adjacent to the west boundary of phase 5.

It is understood that any changes to the planned phasing of the development may require installation of temporary overhead lines to provide appropriate servicing levels.

Telus has advised that infrastructure for telephone service to the area presently exists on the east side of Gaetz Avenue. Therefore, extending service to the plan area will require extension of the existing infrastructure westward along alignments reserved for collector road right-of-way (ie. Kingston Drive at the north end and Kentwood Drive at the south end of the plan area). Should either of these proposed collector roads be re-aligned, easements will be required to complete the extension of service to the area.

#### **4.5 Natural Gas**

Atco Gas advises that they will be able to service the proposed development by extending their existing distribution facilities.

# KENTWOOD NORTHEAST (KINGSGATE)

## FIGURE 5: WATER DISTRIBUTION

SCALE = 1:5000



ROAD ALLOWANCE

- NASP BOUNDARY
- EXISTING MAINS
- 150mm WATER MAIN
- 200mm WATER MAIN
- 250mm OR LARGER WATER MAIN
- FIRE HYDRANT



July, 2022








# KENTWOOD NORTHEAST (KINGSGATE)

## FIGURE 6: SANITARY SEWERS

SCALE = 1:5000



-  NASP BOUNDARY
-  EXISTING MAINS
-  SANITARY SEWER
-  DIRECTION OF FLOW







July, 2022


# KENTWOOD NORTHEAST (KINGSGATE)

## FIGURE 7: STORM SEWERS

SCALE = 1:5000



-  NASP BOUNDARY
-  EXISTING MAINS
-  STORM SEWERS
-  DIRECTION OF FLOW



# KENTWOOD NORTHEAST (KINGSGATE)

## FIGURE 8: OVERLAND DRAINAGE

SCALE = 1:5000



- CATCHMENT BOUNDARY
- DIRECTION OF FLOW
- NASP BOUNDARY



July, 2022

## **5.0 Staging and Development**

Figure 9 shows the proposed staging of development. The area labeled “Existing Development” has been serviced as of the end of 2022. The location of existing utilities dictates phases of development. Market conditions will influence the actual phasing of later developments.

# KENTWOOD NORTHEAST (KINGSGATE)


## FIGURE 9: PHASING

SCALE = 1:5000



Legend:

- PHASE BOUNDARY
- - - NASP BOUNDARY



July, 2022

# KENTWOOD NORTHEAST (KINGSGATE)

## FIGURE 10: PEDESTRIAN CIRCULATION


SCALE = 1:5000



ROAD ALLOWANCE


POTENTIAL PEDESTRIAN PATH  
NASP BOUNDARY

The legend is enclosed in a black-bordered box. It contains two entries: a dashed orange line representing a 'POTENTIAL PEDESTRIAN PATH' and a dashed red line representing a 'NASP BOUNDARY'. Above the legend, the text 'ROAD ALLOWANCE' is written above a set of parallel lines representing a road.



## **APPENDIX A**





**LEGEND**

- THICK HAYAT
- WATER BODIES
- HABITAT AREAS REMOVED TO 1947
- GRASSLAND
- 1947 REMOVED FROM TO 1993
- 1994 STUDY ZONE BOUNDARY (REFER TO ATTACHMENT II FOR ZONE INFORMATION)

**ZONES & HABITAT SITE NUMBER**

- \* ZONE 6
- \* ZONE 7 (5TE, 6TE, 14TE, 18WE)
- \* ZONE 8 (5TE)
- \* ZONE 9 (40WE)
- ZONE 10 (15TE)
- ZONE 11 (20TE)
- ZONE 12 (8TE)
- ZONE 13 (15TE)
- \* ZONE 14 (1TE, 2TE, 5WE)

or E5 - 40WE  
 GRID MAP SECTION OF LAW    HARDSHIP SITE NUMBER    MAPPING CODE  
 W = WETLAND  
 T = TREES  
 E = ECOSPACE

\* THESE ZONES REFERRED TO IN REPORT TEXT  
 ——— REFERS TO APPROXIMATE BOUNDARIES OF ZONES TO BE PROFILED




**FIGURE 2**  
**NORTH KENTWOOD NATURAL (ECOSPACE) AREA**



# KENTWOOD NORTHEAST SCHOOL & PARK SITE


PRELIMINARY DRAFT  
SUBJECT TO CHANGE



KINGSGATE OUTLINE PLAN  
FIGURE 10. STORM POND

DATE: / /

## **APPENDIX B**



DRAINAGE DITCH R/W PLAN 992 0381

UTILITY R/W PLAN 992 0360

BLOCK 8

BLOCK 5  
PLAN 992 0355

CLASS 'B' SOCCER

STORM POND

BLOCK 6  
PLAN 992 0367

CLASS 'B' BALL DIAMOND

KERR CLOSE

KINGSTON DRIVE

REMAINDER OF THE  
SEC. 32, TWP. 38, RGE. 27  
N. E. 1/4

ELEMENTARY SCHOOL SITE

(K-9)

1.30 ha.

LOT 5049  
BLOCK 8  
PLAN 003 2881

PLAN 992 3009  
BLOCK 6

LOT 5048  
PLAN 972 1418

DRAINAGE DITCH R/W PLAN